



NOTES:

1. CASING SPACERS SHOULD BE INSTALLED WITHIN ONE FOOT OF BELL AND SPIGOT JOINT AND ONE IN CENTER OF PIPE.
2. PROVIDE UNIFLANGE RESTRAINED CASING SPACERS 1300 & 1390 OR EQUAL.

PIPE DIA.	CASING SPACER DIMENSION	CASING O.D.	PIPE WALL THICKNESS
6"	13.375"	16"	0.375"
8"	17.125"	18"	0.375"
12"	21.875"	24"	0.375"
16"	28.375"	30"	0.375"
24"	38.250"	40"	0.375"

Kennedy/Jenks Consultants
Engineers & Scientists

165 S Union Boulevard
 Suite 570
 Lakewood, CO 80228
 303 985 3636 TEL

SOUTH ENGLEWOOD SANITATION DISTRICT
www.southenglewood.org

RESTRAINED
 CASING SPACERS
 DETAIL